

**Name of Works: Painting of existing MCA International Cricket Stadium,
Gahunje, Pune**

Terms & Conditions

1	Maharashtra Cricket Association invites tender for painting works as per attached BOQ
2	Tender fee for the said tender shall be Rs. 2,000 and interested bidder shall submit it in the form of cheque drawn in favour of Maharashtra Cricket Association
3	Tenders shall be submitted to Hon. Secretary, Maharashtra Cricket Association by email cricketmaharashtra@yahoo.com or by HARD COPY to Hon. Secretary, Maharashtra Cricket Association, At Post : Gahunje, Teh : Maval, Dist : Pune, Pin Code - 412 101, on or before 11:00 am by July 7th, 2023 <i>*Note : Maharashtra Cricket Association reserves the right to accept or reject the tender.</i>
4	Period of completion shall be 2 months (two months) from the date of commencement as per Work Order. No extension of time shall be granted for reasons whatsoever being time bound project and contractor shall liable to pay compensation for any delay @ 5% of the quoted contract sum for every week or part thereon beyond original date of completion as mentioned in Work order.
5	However, an incentives/bonus shall be awarded to the contractor for early completion of project as under:- (a) 5% of quoted total contract sum for completion before one week prior to original date of completion as mentioned in Work Order (b) 6% of quoted total contract sum for completion before two week prior to original date of completion as mentioned in Work Order (c) 7% of quoted total contract sum for completion before three week prior to original date of completion as mentioned in Work Order
6	Running bill payments shall be made on weekly basis upon certification from appointed Project Management Consultant for the said project
7	Mobilization advance shall be given to the contractor @20% of total contract sum against Bank Guarantee
8	All quoted rates shall be excluding GST. GST shall be paid at actual at then prevailing rate
9	Successful bidder shall submit 0.5% Security Deposit in BG/FDR form in order to release Work Order. Security Deposit shall be returned upon successful completion of the work
10	Any deviation from tendered items shall be approved by Project Management Consultant and Client prior to executing. Rates for the items not included in tender shall be mutually agreed.
11	Client reserves the right to delete or add any item in tender or increase or decrease the quantity of items as per site conditions
12	Water & electricity shall be paid free of cost to contractor by client for said work
13	Free of cost Labour accommodation shall be provided at site by client

**Name of Works: Painting of existing MCA International Cricket Stadium,
Gahunje, Pune**

Sr. No.	Item of Work	Quantity	Unit Rate	Unit Rate	Amount	Amount in Words
1	Providing and applying 2 coats of pearl/luster finish paint of Asian make including primer of approved colour and shade to the existing plastered surface including scaffolding preparing the surface applying birla acrylic wall putti etc. complete.	2,677.50	Square Metre			
2	Removing old paint from steel and other metal surfaces and making the surfaces even with Machine/torch burning scrapping etc.complete. Surface shall be cleaned to the satisfaction of PMC consultant	20,727.25	Square Metre			
3	Providing and applying two coats of synthetic enamel paint of Akzonoble make of approved colour to new/old structural steel work and wood work in buildings including primer including scaffolding up to 5m height from respective FFL if necessary, cleaning and preparing the surface etc. complete. (Scaffolding required above 6m height shall be paid seperately as below)	20,727.25	Square Metre			

**Name of Works: Painting of existing MCA International Cricket Stadium,
Gahunje, Pune**

Sr. No.	Item of Work	Quantity	Unit Rate	Unit Rate	Amount	Amount in Words
4	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/ structure, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40 milimetre diameter Mild Steel tube, placed 1.5 metre centre to centre, horizontal and vertical tubes joint with cup and lock system with Mild Steel Tubes, Mild Steel tube challis, Mild Steel clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. Note:- (1) The elevational area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works. (Area greater than 5m height from respective FFL shall be measured seperately).	3,480.00	Square Metre			
5	Supply of long arm boom lift/ crane with man basket or required boom length to carry out the painting works including mobilisation and demobilisation from site including operator cost, diesel cost all inclusive. Prior approval from PMC required prior to deployment of boom lift/crane	60	Days			
Total Rs.						
Say Rs.						